


## Location Requirements: Attachment 2

- A retail dispensary which is open to the public may only be located within the allowed zoning district(s) under Table 10 of Section 20.08.145, Table 12 of Section 20.08.155, and Table 15 of Section 20.08.195.
- A retail dispensary shall not be established on any parcel containing a dwelling unit, or immediately abutting (sharing a common property line with) a residential zoning district. Residentially zoned does not include mixed-use zoning for purposes of this chapter.
- A retail dispensary shall not be established within five hundred feet from any youth-oriented property.
- A retail dispensary shall not be established within two hundred and fifty feet of any public park (with the exception of West Plaza Park and 3 North Street), public playground, or public library.
- The distances listed above shall be measured between the nearest entrance (ingress/egress to commercial cannabis establishment, e.g., front door/public entry or service door) of the retail dispensary and the nearest property line of the parcel(s) on which the youth-oriented property, public park, public playground, or public library is located, along the shortest route intended and available for public passage (any public road, street, or highway, including footpaths and bicycle paths, or other route provided for the passage of people).



**Legend**

City Limits

**Sensitive Use Parcel**

**Location Type**

- School
- Youth Center
- Child Care
- Library
- Park


**Eligible Parcel Locations**

**COMMERCIAL DISTRICTS**

- CD - Downtown Commercial
- CS - Service Commercial
- MU - Mixed Use

**INDUSTRIAL DISTRICT**

- I - Industrial



## PARCELS ELIGIBLE FOR RETAIL DISPENSARY OR MICROBUSINESS